

PATENT COOPERATION TREATY

PCT

NOTIFICATION OF ELECTION

(PCT Rule 61.2)

From the INTERNATIONAL BUREAU

To:

Assistant Commissioner for Patents
United States Patent and Trademark
Office
Box PCT
Washington, D.C.20231
ETATS-UNIS D'AMERIQUE

in its capacity as elected Office

Date of mailing (day/month/year) 23 May 2000 (23.05.00)	
International application No. PCT/FI99/00825	Applicant's or agent's file reference 2980202PC/su
International filing date (day/month/year) 05 October 1999 (05.10.99)	Priority date (day/month/year) 06 October 1998 (06.10.98)
Applicant HAUMONT, Serge	

1. The designated Office is hereby notified of its election made:

☒ in the demand filed with the International Preliminary Examining Authority on:

26 April 2000 (26.04.00)

☐ in a notice effecting later election filed with the International Bureau on:2. The election ☒ was☐ was not

made before the expiration of 19 months from the priority date or, where Rule 32 applies, within the time limit under Rule 32.2(b).

The International Bureau of WIPO 34, chemin des Colombettes 1211 Geneva 20, Switzerland Facsimile No.: (41-22) 740.14.35	Authorized officer Claudio Borton Telephone No.: (41-22) 338.83.38
---	--

PCT

INTERNATIONAL PRELIMINARY EXAMINATION REPORT

(PCT Article 36 and Rule 70)

15

Applicant's or agent's file reference 2980202PC/su	FOR FURTHER ACTION See Notification of Transmittal of International Preliminary Examination Report (Form PCT/IPEA/416)	
International application No. PCT/FI99/00825	International filing date (day/month/year) 05.10.1999	Priority date (day/month/year) 06.10.1998
International Patent Classification (IPC) or national classification and IPC ⁷ H 04 Q 7/38, H 04 L 12/56		
Applicant Nokia Networks OY et al		

1. This international preliminary examination report has been prepared by this International Preliminary Examining Authority and is transmitted to the applicant according to Article 36.
2. This REPORT consists of a total of 4 sheets, including this cover sheet.
- ☐ This report is also accompanied by ANNEXES, i.e., sheets of the description, claims and/or drawings which have been amended and are the basis for this report and/or sheets containing rectifications made before this Authority (see Rule 70.16 and Section 607 of the Administrative Instructions under the PCT).

These annexes consist of a total of _____ sheets.

3. This report contains indications relating to the following items:

- I ☒ Basis of the report
- II ☐ Priority
- III ☐ Non-establishment of opinion with regard to novelty, inventive step and industrial applicability
- IV ☐ Lack of unity of invention
- V ☒ Reasoned statement under Article 35(2) with regard to novelty, inventive step or industrial applicability; citations and explanations supporting such statement
- VI ☐ Certain documents cited
- VII ☐ Certain defects in the international application
- VIII ☐ Certain observations on the international application

CORRECTED
VERSION

Date of submission of the demand 26.04.2000	Date of completion of this report 13.12.2000
Name and mailing address of the IPEA/SE Patent- och registreringsverket Box 5055 S-102 42 STOCKHOLM Facsimile No. 08-667 72 88	Authorized officer Agneta Änggård/Els Telephone No. 08-782 25 00

CORRECTED

INTERNATIONAL PRELIMINARY EXAMINATION REPORT

International application No.

PCT/FI99/00825

I. Basis of the report

1. With regard to the elements of the international application:*

☒ the international application as originally filed

☐ the description:

pages _____, as originally filed

pages _____, filed with the demand

pages _____, filed with the letter of _____

☐ the claims:

pages _____, as originally filed

pages _____, as amended (together with any statement) under article 19

pages _____, filed with the demand

pages _____, filed with the letter of _____

☐ the drawings:

pages _____, as originally filed

pages _____, filed with the demand

pages _____, filed with the letter of _____

☐ the sequence listing part of the description:

pages _____, as originally filed

pages _____, filed with the demand

pages _____, filed with the letter of _____

2. With regard to the language, all the elements marked above were available or furnished to this Authority in the language in which the international application was filed, unless otherwise indicated under this item.

These elements were available or furnished to this Authority in the following language _____ which is:

☐ the language of a translation furnished for the purposes of international search (under Rule 23.1(b)).

☐ the language of publication of the international application (under Rule 48.3(b)).

☐ the language of the translation furnished for the purposes of international preliminary examination (under Rules 55.2 and/or 55.3).

3. With regard to any nucleotide and/or amino acid sequence disclosed in the international application, the international preliminary examination was carried out on the basis of the sequence listing:

☐ contained in the international application in written form.

☐ filed together with the international application in computer readable form.

☐ furnished subsequently to this Authority in written form.

☐ furnished subsequently to this Authority in computer readable form.

☐ The statement that the subsequently furnished written sequence listing does not go beyond the disclosure in the international application as filed has been furnished.

☐ The statement that the information recorded in computer readable form is identical to the written sequence listing has been furnished.

4. ☐ The amendments have resulted in the cancellation of:

☐ the description, pages _____

☐ the claims, Nos. _____

☐ the drawings, sheet/fig _____

5. ☐ This report has been established as if (some of) the amendments had not been made, since they have been considered to go beyond the disclosure as filed, as indicated in the Supplemental Box (Rule 70.2 (c)).**

* Replacement sheets which have been furnished to the receiving Office in response to an invitation under Article 14 are referred to in this report as "originally filed" and are annexed to this report since they do not contain amendments (Rules 70.16 and 70.17).

** Any replacement sheet containing such amendments must be referred to under item I and annexed to this report.

INTERNATIONAL PRELIMINARY EXAMINATION REPORT

International application No.

PCT/FI99/00825

V. Reasoned statement under Article 35(2) with regard to novelty, inventive step or industrial applicability; citations and explanations supporting such statement

1. Statement

Novelty (N)	Claims	<u>1-18</u>	YES
	Claims	_____	NO
Inventive step (IS)	Claims	<u>1-18</u>	YES
	Claims	_____	NO
Industrial applicability (IA)	Claims	<u>1-18</u>	YES
	Claims	_____	NO

2. Citations and explanations (Rule 70.7)

The invention relates to a packet radio networks in general and in particular to supporting mobility in packet networks. The object of the invention is to minimize the problems and disadvantages resulting from prior art temporary identity (TLLI/TMSI) allocation method.

The basic idea of the invention is that the network element allocating the temporary identity encodes its own identifier into the temporary identity. This is achieved by allocating a temporary identity (TLLI) in a cellular network to a mobile station (MS) by a first network element (SGSN, BSC, RNC) which has an identifier of its own, characterized in that the temporary identity (TLLI) comprises at least part of an identifier (NEI) indicating the first network element.

The following documents were referred to in the International Search Report:

- (1) EP 0859331
- (2) WO 9916036
- (3) WO 9733403

(1) refers to a method for providing a unique temporary identification of a mobile station. The new identity is used as identification on the radio interface, identification within the current SGSN and for identification of the old SGSN.

(2) refers to position-responsive, hierarchically selectable information presentation system and control program.

(3) refers to an improving security of packet-mode transmission in a mobile communication system.

.../...

CORRECTED

INTERNATIONAL PRELIMINARY EXAMINATION REPORT

International application No.

PCT/FI99/00825

Supplemental Box

(To be used when the space in any of the preceding boxes is not sufficient)

Continuation of: V

The cited documents disclose different solutions for supporting mobility in packet radio networks representing the general state of the art, but are not considered to be of particular relevance.

Thus, the claimed invention fulfils the requirements of novelty, inventive step and industrial applicability.

CORRECTED

PCT

INTERNATIONAL PRELIMINARY EXAMINATION REPORT

(PCT Article 36 and Rule 70)

15

Applicant's or agent's file reference 2980202PC/su	FOR FURTHER ACTION	See Notification of Transmittal of International Preliminary Examination Report (Form PCT/IPEA/416)
International application No. PCT/FI99/00825	International filing date (day/month/year) 05.10.1999	Priority date (day/month/year) 06.10.1998
International Patent Classification (IPC) or national classification and IPC7 H 04 Q 7/38, H 04 L 12/56		
Applicant Nokia Networks OY et al		

1. This international preliminary examination report has been prepared by this International Preliminary Examining Authority and is transmitted to the applicant according to Article 36.
2. This REPORT consists of a total of 4 sheets, including this cover sheet.
- ☐ This report is also accompanied by ANNEXES, i.e., sheets of the description, claims and/or drawings which have been amended and are the basis for this report and/or sheets containing rectifications made before this Authority (see Rule 70.16 and Section 607 of the Administrative Instructions under the PCT).
- These annexes consist of a total of _____ sheets.

3. This report contains indications relating to the following items:

- I ☒ Basis of the report
- II ☐ Priority
- III ☐ Non-establishment of opinion with regard to novelty, inventive step and industrial applicability
- IV ☐ Lack of unity of invention
- V ☒ Reasoned statement under Article 35(2) with regard to novelty, inventive step or industrial applicability; citations and explanations supporting such statement
- VI ☐ Certain documents cited
- VII ☐ Certain defects in the international application
- VIII ☐ Certain observations on the international application

Date of submission of the demand 26.04.2000	Date of completion of this report 13.12.2000
Name and mailing address of the IPEA/SE Patent- och registreringsverket Box 5055 S-102 42 STOCKHOLM Facsimile No. 08-667 72 88	Authorized officer Agneta Änggård/Els Telephone No. 08-782 25 00

INTERNATIONAL PRELIMINARY EXAMINATION REPORT

International application No.

PCT/FI99/00825

I. Basis of the report

1. With regard to the elements of the international application:*

- ☒ the international application as originally filed
- ☐ the description:
 pages _____, as originally filed
 pages _____, filed with the demand
 pages _____, filed with the letter of _____
- ☐ the claims:
 pages _____, as originally filed
 pages _____, as amended (together with any statement) under article 19
 pages _____, filed with the demand
 pages _____, filed with the letter of _____
- ☐ the drawings:
 pages _____, as originally filed
 pages _____, filed with the demand
 pages _____, filed with the letter of _____
- ☐ the sequence listing part of the description:
 pages _____, as originally filed
 pages _____, filed with the demand
 pages _____, filed with the letter of _____

2. With regard to the language, all the elements marked above were available or furnished to this Authority in the language in which the international application was filed, unless otherwise indicated under this item.

These elements were available or furnished to this Authority in the following language _____ which is:

- ☐ the language of a translation furnished for the purposes of international search (under Rule 23.1(b)).
- ☐ the language of publication of the international application (under Rule 48.3(b)).
- ☐ the language of the translation furnished for the purposes of international preliminary examination (under Rules 55.2 and/or 55.3).

3. With regard to any nucleotide and/or amino acid sequence disclosed in the international application, the international preliminary examination was carried out on the basis of the sequence listing:

- ☐ contained in the international application in written form.
- ☐ filed together with the international application in computer readable form.
- ☐ furnished subsequently to this Authority in written form.
- ☐ furnished subsequently to this Authority in computer readable form.
- ☐ The statement that the subsequently furnished written sequence listing does not go beyond the disclosure in the international application as filed has been furnished.
- ☐ The statement that the information recorded in computer readable form is identical to the written sequence listing has been furnished.

4. ☐ The amendments have resulted in the cancellation of:

- ☐ the description, pages _____
- ☐ the claims, Nos. _____
- ☐ the drawings, sheet/fig _____

5. ☐ This report has been established as if (some of) the amendments had not been made, since they have been considered to go beyond the disclosure as filed, as indicated in the Supplemental Box (Rule 70.2 (c)).**

* Replacement sheets which have been furnished to the receiving Office in response to an invitation under Article 14 are referred to in this report as "originally filed" and are annexed to this report since they do not contain amendments (Rules 70.16 and 70.17).

** Any replacement sheet containing such amendments must be referred to under item I and annexed to this report.

INTERNATIONAL PRELIMINARY EXAMINATION REPORT

International application No.

PCT/FI99/00825

V. Reasoned statement under Article 35(2) with regard to novelty, inventive step or industrial applicability; citations and explanations supporting such statement

1. Statement

Novelty (N)	Claims	<u>1-18</u>	YES
	Claims		NO
Inventive step (IS)	Claims	<u>1-18</u>	YES
	Claims		NO
Industrial applicability (IA)	Claims	<u>1-18</u>	YES
	Claims		NO

2. Citations and explanations (Rule 70.7)

D2 makes known an implant for use in bone augmentation. The implant is made of a prosthetic filling material enclosed in a hollow casing. The casing is made of a resorbable and porous material that allows tissue growth. The difference between the invention and this document is that D2 does not disclose a mixture of granular and biological material, further containing a component making the enclosed material formable and mouldable.

Consequently, the cited documents only disclose the general state of the art, and are not considered to be of particular relevance. Thus, the invention claimed in claims 1-9 is considered to fulfil the requirements of novelty, inventive step and industrial applicability.

However, claims 10-18 are directed to a method of treatment of the human or animal body. Claims of this kind may be accepted and examined in some countries. Owing to the difference in national practice and laws, it is not possible for the International Preliminary Examining Authority to give a valid statement on such claims. See also PCT Rule 67.1 (iv).

(2) refers to a position-responsive, hierarchically selectable information presentation system and control program.

(3) refers to an improving security of packet-mode transmission in a mobile communication system.

.../...

INTERNATIONAL PRELIMINARY EXAMINATION REPORT

International application No.

PCT/FI99/00825

Supplemental Box

(To be used when the space in any of the preceding boxes is not sufficient)

Continuation of: V

The cited documents disclose different solutions for supporting mobility in packet radio networks representing the general state of the art, but are not considered to be of particular relevance.

Thus, the claimed invention fulfils the requirements of novelty, inventive step and industrial applicability.

RECORD COPY

1/4

PCT REQUEST

2980202PC/su

Original (for SUBMISSION) - printed on 05.10.1999 01:42:32 PM

0	For receiving Office use only	
0-1	International Application No.	PCT/FI 99 / 0 0 8 25
0-2	International Filing Date	05 OCT 1999 (05.10.99)
0-3	Name of receiving Office and "PCT International Application"	The Finnish Patent Office PCT International Application
0-4	Form - PCT/RO/101 PCT Request	
0-4-1	Prepared using	PCT-EASY Version 2.84 (updated 01.07.1999)
0-5	Petition The undersigned requests that the present international application be processed according to the Patent Cooperation Treaty	
0-6	Receiving Office (specified by the applicant)	National Board of Patents and Registration (Finland) (RO/FI)
0-7	Applicant's or agent's file reference	2980202PC/su
I	Title of invention	IDENTIFYING A MOBILE STATION IN A PACKET RADIO NETWORK
II	Applicant	
II-1	This person is:	applicant only
II-2	Applicant for	all designated States except US
II-4	Name	NOKIA NETWORKS OY
II-5	Address:	Keilalahdentie 4 FIN-02150 Espoo Finland
II-6	State of nationality	FI
II-7	State of residence	FI
III-1	Applicant and/or inventor	
III-1-1	This person is:	applicant and inventor
III-1-2	Applicant for	US only
III-1-4	Name (LAST, First)	HAUMONT, Serge
III-1-5	Address:	Riistavuorenkuja 3 B 10 FIN-00320 Helsinki Finland
III-1-6	State of nationality	FR
III-1-7	State of residence	FI

PCT REQUEST


2980202PC/su

Original (for SUBMISSION) - printed on 05.10.1999 01:42:32 PM

IV-1	Agent or common representative; or address for correspondence The person identified below is hereby/has been appointed to act on behalf of the applicant(s) before the competent International Authorities as:	agent
IV-1-1	Name	KOLSTER OY AB
IV-1-2	Address:	Iso Roobertinkatu 23 P.O. Box 148 FIN-00121 Helsinki Finland
IV-1-3	Telephone No.	+ 358 9 618 821
IV-1-4	Facsimile No.	+ 358 9 602 244
IV-1-5	e-mail	Kolster@Kolster.Fi
V	Designation of States	
V-1	Regional Patent (other kinds of protection or treatment, if any, are specified between parentheses after the designation(s) concerned)	AP: GH GM KE LS MW SD SL SZ UG ZW and any other State which is a Contracting State of the Harare Protocol and of the PCT EA: AM AZ BY KG KZ MD RU TJ TM and any other State which is a Contracting State of the Eurasian Patent Convention and of the PCT EP: AT BE CH&LI CY DE DK ES FI FR GB GR IE IT LU MC NL PT SE and any other State which is a Contracting State of the European Patent Convention and of the PCT OA: BF BJ CF CG CI CM GA GN GW ML MR NE SN TD TG and any other State which is a member State of OAPI and a Contracting State of the PCT
V-2	National Patent (other kinds of protection or treatment, if any, are specified between parentheses after the designation(s) concerned)	AE AL AM AT (patent and utility model) AU AZ BA BB BG BR BY CA CH&LI CN CR CU CZ (patent and utility model) DE (patent and utility model) DK (patent and utility model) DM EE (patent and utility model) ES FI (patent and utility model) GB GD GE GH GM HR HU ID IL IN IS JP KE KG KP KR KZ LC LK LR LS LT LU LV MD MG MK MN MW MX NO NZ PL PT RO RU SD SE SG SI SK (patent and utility model) SL TJ TM TR TT TZ UA UG US UZ VN YU ZA ZW

PCT REQUEST

Original (for SUBMISSION) - printed on 05.10.1999 01:42:32 PM

V-5	Precautionary Designation Statement In addition to the designations made under items V-1, V-2 and V-3, the applicant also makes under Rule 4.9(b) all designations which would be permitted under the PCT except any designation(s) of the State(s) indicated under item V-6 below. The applicant declares that those additional designations are subject to confirmation and that any designation which is not confirmed before the expiration of 15 months from the priority date is to be regarded as withdrawn by the applicant at the expiration of that time limit.		
V-6	Exclusion(s) from precautionary designations NONE		
VI-1	Priority claim of earlier national application		
VI-1-1	Filing date	06 October 1998 (06.10.1998)	
VI-1-2	Number	982166	
VI-1-3	Country	FI	
VI-2	Priority document request The receiving Office is requested to prepare and transmit to the International Bureau a certified copy of the earlier application(s) identified above as item(s):		
VI-2	VI-1		
VII-1	International Searching Authority Chosen Swedish Patent Office (ISA/SE)		
VIII	Check list	number of sheets	electronic file(s) attached
VIII-1	Request	4	-
VIII-2	Description	15	-
VIII-3	Claims	3	-
VIII-4	Abstract	1	2980202p.txt
VIII-5	Drawings	3	-
VIII-7	TOTAL	26	
VIII-8	Accompanying items	paper document(s) attached	electronic file(s) attached
VIII-8	Fee calculation sheet	✓	-
VIII-9	Separate signed power of attorney	✓	-
VIII-16	PCT-EASY diskette	-	diskette
VIII-17	Other (specified):	Copy of Official Action	-
VIII-18	Figure of the drawings which should accompany the abstract	3	
VIII-19	Language of filing of the international application	English	
IX-1	Signature of applicant or agent	 Leo Lehtonen	
IX-1-1	Name	KOLSTER OY AB	

FOR RECEIVING OFFICE USE ONLY

10-1	Date of actual receipt of the purported international application	05 OCT 1999	(05 -10- 1999)
------	---	-------------	------------------

PCT REQUEST

2980202PC/su

Original (for SUBMISSION) - printed on 05.10.1999 01:42:32 PM

10-2	Drawings:	
10-2-1	Received	
10-2-2	Not received	
10-3	Corrected date of actual receipt due to later but timely received papers or drawings completing the purported international application	
10-4	Date of timely receipt of the required corrections under PCT Article 11(2)	
10-5	International Searching Authority	ISA/SE
10-6	Transmittal of search copy delayed until search fee is paid	

FOR INTERNATIONAL BUREAU USE ONLY

11-1	Date of receipt of the record copy by the International Bureau	
------	--	--




INTERNATIONAL APPLICATION PUBLISHED UNDER THE PATENT COOPERATION TREATY (PCT)

(51) International Patent Classification ⁷ : H04Q 7/38, H04L 12/56		A1	(11) International Publication Number: WO 00/21319
			(43) International Publication Date: 13 April 2000 (13.04.00)
(21) International Application Number: PCT/FI99/00825 (22) International Filing Date: 5 October 1999 (05.10.99) (30) Priority Data: 982166 6 October 1998 (06.10.98) FI (71) Applicant (for all designated States except US): NOKIA NETWORKS OY [FI/FI]; Keilalahdentie 4, FIN-02150 Espoo (FI). (72) Inventor; and (75) Inventor/Applicant (for US only): HAUMONT, Serge [FR/FI]; Riistavuorenkuja 3 B 10, FIN-00320 Helsinki (FI). (74) Agent: KOLSTER OY AB; Iso Roobertinkatu 23, P.O. Box 148, FIN-00121 Helsinki (FI).		(81) Designated States: AE, AL, AM, AT, AT (Utility model), AU, AZ, BA, BB, BG, BR, BY, CA, CH, CN, CR, CU, CZ, CZ (Utility model), DE, DE (Utility model), DK, DK (Utility model), DM, EE, EE (Utility model), ES, FI, FI (Utility model), GB, GD, GE, GH, GM, HR, HU, ID, IL, IN, IS, JP, KE, KG, KP, KR, KZ, LC, LK, LR, LS, LT, LU, LV, MD, MG, MK, MN, MW, MX, NO, NZ, PL, PT, RO, RU, SD, SE, SG, SI, SK, SK (Utility model), SL, TJ, TM, TR, TT, TZ, UA, UG, US, UZ, VN, YU, ZA, ZW, ARIPO patent (GH, GM, KE, LS, MW, SD, SL, SZ, TZ, UG, ZW), Eurasian patent (AM, AZ, BY, KG, KZ, MD, RU, TJ, TM), European patent (AT, BE, CH, CY, DE, DK, ES, FI, FR, GB, GR, IE, IT, LU, MC, NL, PT, SE), OAPI patent (BF, BJ, CF, CG, CI, CM, GA, GN, GW, ML, MR, NE, SN, TD, TG).	
		Published With international search report. Before the expiration of the time limit for amending the claims and to be republished in the event of the receipt of amendments.	

(54) Title: IDENTIFYING A MOBILE STATION IN A PACKET RADIO NETWORK

(57) Abstract

In conventional cellular systems, the identifier of network elements (SGSN) allocating a temporary identity (TLLI) to a mobile station (MS) can be derived from the identities of the cells they serve. In the future, this assumption may no longer be valid. One paging area could be handled by several network elements, such as SGSN nodes, or one network element could serve many paging areas. When the mobile station changes its paging area, the new supporting network element may have trouble in determining the old supporting network element on the basis of the paging area identifier. It is also possible for two supporting network elements to allocate the same TLLI to two different mobile stations. Therefore the network element (SGSN, BSC, RNC) allocating a temporary identity (TLLI) to a mobile station (MS) should incorporate at least part of its own identifier (NEI) into the temporary identity (TLLI).



FOR THE PURPOSES OF INFORMATION ONLY

Codes used to identify States party to the PCT on the front pages of pamphlets publishing international applications under the PCT.

AL	Albania	ES	Spain	LS	Lesotho	SI	Slovenia
AM	Armenia	FI	Finland	LT	Lithuania	SK	Slovakia
AT	Austria	FR	France	LU	Luxembourg	SN	Senegal
AU	Australia	GA	Gabon	LV	Latvia	SZ	Swaziland
AZ	Azerbaijan	GB	United Kingdom	MC	Monaco	TD	Chad
BA	Bosnia and Herzegovina	GE	Georgia	MD	Republic of Moldova	TG	Togo
BB	Barbados	GH	Ghana	MG	Madagascar	TJ	Tajikistan
BE	Belgium	GN	Guinea	MK	The former Yugoslav Republic of Macedonia	TM	Turkmenistan
BF	Burkina Faso	GR	Greece			TR	Turkey
BG	Bulgaria	HU	Hungary	ML	Mali	TT	Trinidad and Tobago
BJ	Benin	IE	Ireland	MN	Mongolia	UA	Ukraine
BR	Brazil	IL	Israel	MR	Mauritania	UG	Uganda
BY	Belarus	IS	Iceland	MW	Malawi	US	United States of America
CA	Canada	IT	Italy	MX	Mexico	UZ	Uzbekistan
CF	Central African Republic	JP	Japan	NE	Niger	VN	Viet Nam
CG	Congo	KE	Kenya	NL	Netherlands	YU	Yugoslavia
CH	Switzerland	KG	Kyrgyzstan	NO	Norway	ZW	Zimbabwe
CI	Côte d'Ivoire	KP	Democratic People's Republic of Korea	NZ	New Zealand		
CM	Cameroon			PL	Poland		
CN	China	KR	Republic of Korea	PT	Portugal		
CU	Cuba	KZ	Kazakhstan	RO	Romania		
CZ	Czech Republic	LC	Saint Lucia	RU	Russian Federation		
DE	Germany	LI	Liechtenstein	SD	Sudan		
DK	Denmark	LK	Sri Lanka	SE	Sweden		
EE	Estonia	LR	Liberia	SG	Singapore		

IDENTIFYING A MOBILE STATION IN A PACKET RADIO NETWORK

BACKGROUND OF THE INVENTION

The invention relates to packet radio networks in general, and in particular to supporting mobility in packet radio networks.

5 General packet radio service GPRS is a new service in the GSM system, and is one of the objects of the standardisation work of the GSM phase 2+ at the ETSI (European Telecommunication Standard Institute). The GPRS operational environment comprises one or more subnetwork service areas, which are interconnected by a GPRS backbone network. A subnetwork
10 comprises a number of packet data service nodes SN, which in this application will be referred to as serving GPRS support nodes SGSN, each of which is connected to the GSM mobile communication network (typically to base station systems) in such a way that it can provide a packet service for mobile data terminals via several base stations, i.e. cells. The intermediate mobile
15 communication network provides packet-switched data transmission between a support node and mobile data terminals. Different subnetworks are in turn connected to an external data network, e.g. to a public switched data network PSPDN, via GPRS gateway support nodes GGSN. The GPRS service thus allows packet data transmission between mobile data terminals and external
20 data networks when the GSM network functions as an access network.

Figure 1A illustrates a GPRS packet radio network implemented in the GSM system. The basic structure of the GSM system comprises two elements: a base station system BSS and a network subsystem NSS. The BSS and mobile stations MS communicate over radio links. In the base station
25 system BSS each cell is served by a base station BTS. A number of base stations are connected to a base station controller BSC, which controls the radio frequencies and channels used by the BTS. Base station controllers BSC are connected to a mobile services switching centre MSC. As regards a more detailed description of the GSM system, reference is made to the
30 ETSI/GSM recommendations and *The GSM System for Mobile Communications*, M. Mouly and M. Pautet, Palaiseau, France, 1992, ISBN:2-957190-07-7.

In the system shown in Figure 1 the GPRS system connected to the GSM network comprises one GPRS network, which in turn comprises two
35 serving GPRS support nodes (SGSN) and one GPRS gateway support node (GGSN). The different support nodes SGSN and GGSN are interconnected by

an intra-operator backbone network. In a GPRS network there may be any number of support nodes and gateway support nodes.

The serving GPRS support node SGSN is a node which serves a mobile station MS. Each support node SGSN controls a packet data service
5 within the area of one or more cells in a cellular packet radio network, and therefore each support node SGSN is connected (via a Gb interface) to a certain local element of the GSM system. This connection is typically established to the base station system BSS, i.e. to base station controllers BSC or to a base station BTS. A mobile station MS located in a cell
10 communicates with a base station BTS over a radio interface and further with the support node SGSN to the service area of which the cell belongs through the mobile communication network. In principle, the mobile communication network between the support node SGSN and the mobile station MS only relays packets between these two. To realise this, the mobile communication
15 network provides packet-switched transmission of data packets between the mobile station MS and the serving support node SGSN. It has to be noted that the mobile communication network only provides a physical connection between the mobile station MS and the support node SGSN, and thus its exact function and structure are not significant with respect to the invention.
20 The SGSN is also provided with a signalling interface Gs (e.g. an SS7 signalling connection) to the visitor location register VLR of the mobile communication network and/or to the mobile services switching centre. The SGSN may transmit location information to the MSC/VLR and/or receive requests for paging a GPRS subscriber from the MSC/VLR.

25 When the MS attaches to the GPRS network, i.e. in a GPRS attach procedure, the SGSN creates a mobility management (MM) context containing, for example, information related to the mobility and security of the MS. In connection with a PDP activation procedure the SGSN creates a PDP (packet data protocol) context which is used for routing purposes within the
30 GPRS network with the GGSN which the GPRS subscriber uses.

The GPRS gateway support node GGSN connects an operator's GPRS network to other operators' GPRS systems and to data networks 11 - 12, such as an inter-operator backbone network, IP network (Internet) or X.25 network. The GGSN includes GPRS subscribers' PDP addresses and routing
35 information, i.e. SGSN addresses. Routing information is used for tunneling protocol data units PDU from data network 11 to the current switching point of

the MS, i.e. to the serving SGSN. Functionalities of the SGSN and GGSN nodes can be integrated into one physical node.

A home location register HLR of the GSM network contains GPRS subscriber data and routing information and it maps the subscriber's IMSI into one or more pairs of the PDP type and PDP address. The HLR also maps each pair of PDP type and PDP address into one or more GGSNs. The SGSN has a Gr interface to the HLR (a direct signalling connection or a connection via an internal backbone network 13). The HLR of a roaming MS may be in a different mobile communication network than the serving SGSN.

10 An intra-operator backbone network 13, which interconnects the SGSN and GGSN equipment of an operator, can be implemented, for example, by means of a local network, such as an IP network. It should be noted that a GPRS network of an operator can also be implemented without the intra-operator backbone network, e.g. by providing all features in one
15 computer.

An inter-operator backbone network is a network via which different operators' gateway support nodes GGSN can communicate with one another.

Figure 1B illustrates protocol layers of the signalling level between an MS and an SGSN. In the GPRS system, layered protocol structures, known as a transmission level and a signalling level, have been defined for
20 transmitting user information and signalling. A transmission level has a layered protocol structure providing transmission of user information together with control procedures of data transmission related to it (e.g. flow control, error detection, error correction and error recovery). A signalling level consists of
25 protocols which are used for controlling and supporting the functions of the transmission level, such as controlling access to the GPRS network (Attach and Detach) and controlling the routing path of the established network connection in order to support user mobility. The protocol layers of the transmission level are identical with those of Figure 2 up to protocol layer
30 SNDCP, above which there is a protocol of the GPRS backbone network (e.g. the Internet Protocol IP) between the MS and the GGSN (instead of protocol L3MM). The protocol layers illustrated in Figure 1B are:

- The Layer 3 Mobility Management (L3MM): this protocol supports the functionality of mobility management, e.g. GPRS Attach, GPRS Detach,
35 security, routing area update, location area update, activation of a PDP context, and deactivation of a PDP context.

- The Subnetwork Dependent Convergence Protocol (SNDCP) supports transmission of protocol data units (N-PDU) of a network layer between an MS and an SGSN. The SNDCP layer, for example, manages ciphering and compression of N-PDUs.

5 - The Logical Link Control (LLC): this layer provides a very reliable logical link. The LLC is independent of the radio interface protocols mentioned below.

- The LLC Relay: this function relays LLC protocol data units (PDU) between an MS-BSS interface (Um) and a BSS-SGSN interface (Gb).

10 - The Base Station Subsystem GPRS Protocol (BSSGP): this layer transmits routing information and information related to QoS between a BSS and an SGSS.

- The Frame Relay, which is used over the Gb interface. A semipermanent connection for which several subscribers' LLC PDUs are
15 multiplexed is established between the SGSN and the BSS.

- The Radio Link Control (RLC): this layer provides a reliable link independent of radio solutions.

- The Medium Access Control (MAC): this one controls access signalling (request and grant) related to a radio channel and mapping of LLC
20 frames onto a physical GSM channel.

With respect to the invention, the most interesting protocol layers are the LCC and the L3MM. The function of the LLC layer can be described as follows: the LLC layer functions above the RLC layer in the reference architecture and establishes a logical link between the MS and its serving
25 SGSN. With respect to the function of the LCC the most important requirements are a reliable management of the LCC frame relay and support for point-to-point and point-to-multipoint addressing.

A service access point (SAP) of the logical link layer is a point where the LLC layer provides services for the layer 3 protocols (the SNDCP
30 layer in Figure 1B). The link of the LLC layer is identified with a data link connection identifier (DLCI), which is transmitted in the address field of each LLC frame. The DLCI consists of two elements: A Service Access Point Identifier (SAPI) and a Temporary Logical Link Identity TLLI. When a more general expression of a TLLI is needed, the term 'temporary identity' will be
35 used.

When a user attaches to a GPRS network, a logical link is established between the MS and the SGSN. Thus it can be said that the MS has a call in progress. This logical link has a route between the MS and the SGSN, indicated with the TLLI identifier. Thus the TLLI is a temporary
5 identifier, which the SGSN allocates for a certain logical link and IMSI. The SGSN sends the TLLI to the MS in connection with the establishment of a logical link, and it is used as an identifier in later signalling and data transmission over this logical link.

Data transmission over a logical link is carried out as explained in
10 the following. Data to be transmitted to or from an MS is processed with an SNDCP function and transmitted to the LLC layer. The LLC layer inserts the data in the information field of LLC frames. The address field of a frame includes e.g. a TLLI. The LLC layer relays the data to the RLC, which deletes unnecessary information and segments the data into a form compatible with
15 the MAC. The MAC layer activates radio resource processes in order to obtain a radio traffic path for transmission. A corresponding MAC unit on the other side of the radio traffic path receives the data and relays it upwards to the LLC layer. Finally, the data is transmitted from the LLC layer to the SNDCP, where the user data is restored completely and relayed to the next protocol layer.

20 Three different MM states of the MS are typical of the mobility management (MM) of a GPRS subscriber: an idle state, a standby state and a ready state. Each state represents a certain functionality and information level, which has been allocated to the MS and the SGSN. Information sets related to these states, called MM contexts, are stored in the SGSN and the MS. The
25 context of the SGSN contains subscriber data, such as the subscriber's IMSI, TLLI and location and routing information, etc.

In the standby and ready states the MS is attached to the GPRS network. In the GPRS network, a dynamic MM context has been created for the MS, and a logical link LLC (Logical Link Control) is established between
30 the MS and the SGSN in a protocol layer. The ready state is the actual data transmission state in which the MS can transmit and receive user data. The MS switches from the standby state to the ready state either when the GPRS network pages the MS or when the MS initiates data transmission or signalling. The MS may remain in the ready state (for a period set with a timer)
35 even when no user data is transmitted nor signalling performed.

In the standby and ready states the MS also has one or more PDP contexts (Packet Data Protocol), which are stored in the serving SGSN in connection with the MM context. The PDP context defines different data transmission parameters, such as the PDP type (e.g. X.25 or IP), PDP address (e.g. X.121 address), quality of service QoS and NSAPI. The MS
5 activates the PDU context with a specific message, Activate PDP Context Request, in which it gives information on the TLLI, PDP type, PDP address, required QoS and NSAPI. When the MS roams to the area of a new SGSN, the new SGSN requests MM and PDP contexts from the old SGSN.

10 For mobility management, logical routing areas have been defined for the GPRS network. A routing area (RA) is an area defined by an operator, comprising one or more cells. Usually, one SGSN serves several routing areas. A routing area is used for determining the location of the MS in the standby state. If the location of the MS is not known in terms of a specific cell,
15 signalling is started with a GPRS page within one routing area RA. In other words, a paging area is normally also a routing area in a GPRS system, and a location area in a current GSM system.

The MS performs a routing area update procedure in order to support mobility of a packet-switched logical link. In the ready state the MS
20 initiates the procedure when a new cell is selected, the routing area changes or an update timer of a cyclic routing area expires. The radio network (PLMN) is arranged to transmit a sufficient amount of system information to the MS so that it can detect when it enters a new cell or a new routing area RA and to determine when it is to carry out cyclic routing area updates. The MS detects
25 that it has entered a new cell by comparing cyclically the cell identity (Cell ID) which is stored in its MM context with the cell identity which is received from the network. Correspondingly, the MS detects that it has entered a new routing area RA by comparing the routing area identifier stored in its MM context with the routing area identifier received from the network. When the MS selects a
30 new cell, it stores the cell identity and routing area in its MM context.

All the procedures described above (e.g. attach, detach, routing area update and activation/deactivation of the PDP context) for creating and updating MM and PDP contexts and establishing a logical link are procedures activated by the MS. In connection with a routing area update the MS,
35 however, carries out an update to the new routing area without being able to conclude on the basis of the routing area information broadcast by cells

whether the SGSN serving the new cell is the same as the SGSN that served the old cell. On the basis of the old routing area information transmitted by the MS in an update message the new SGSN detects that a routing area update is in progress between two SGSN nodes, and it activates the necessary
5 interrogation to the old SGSN in order to create new MM and PDP contexts for the MS to the new SGSN. Since the SGSN has changed, the logical link should be re-established between the MS and the new SGSN.

Figure 2, which is originally Figure 17 of ETSI Recommendation GSM 03.60 (version 6.0.0), is a signalling diagram illustrating (mainly) a prior
10 art attach procedure. The mobile station's former support node SGSN and mobile switching centre MSC/VLR are called "old" and the current ones are called "new". In step 2-1 the MS sends an ATTACH REQUEST. Steps 2-2 to 2-5 are not necessary for understanding the invention and these steps will not be described. In step 2-6a the new node, SGSN2, sends an UPDATE LOCATION
15 message to the HLR, which in step 2-6b sends a CANCEL LOCATION to the old SGSN1. In step 2-6c the old SGSN1 acknowledges (=ACK). In step 2-6d the new SGSN2 receives the subscriber's data in a message INSERT SUBSCRIBER DATA and acknowledges in step 2-6e. In step 2-6f the new SGSN2 receives from the HLR an acknowledgement to the location update sent in step 2-6a.

20 In step 2-7a the new SGSN2 sends a LOCATION UPDATING REQUEST to the new MSC/VLR. Steps 2-7b through 2-7g correspond to steps 2-6a through 2-6f. In step 2-7h the new SGSN2 receives from the new MSC an acknowledgement to the location update sent in step 2-7a. In step 2-8 the new SGSN2 reports to the MS that the ATTACH REQUEST sent in step 2-1 has been
25 accepted. The remaining steps are not relevant to the invention and will not be described.

Figure 3, which is originally Figure 26 of ETSI Recommendation GSM 03.60 (version 6.0.0), is a signalling diagram illustrating (mainly) a prior
30 art routing area update procedure. In an inter-SGSN routing area update procedure the serving SGSN changes and the MS should be informed of the change so that the MS can initiate a local procedure or a network procedure for updating a logical link. In the following description, the reference numbers refer to messages or events shown in Figure 3.

35 3-1. The MS sends a routing area update request to the new SGSN2. This message includes the temporary logical link identity TLLI, the cell identity of the new cell Cell_id, the routing area identifier of the old routing

area RA_id, and the routing area identifier of the new routing area RA_id. If load is to be decreased in the radio interface, the cell identity Cell_id is not added until in the base station system BSS.

3-2. The new SGSN2 detects that the old routing area belongs to
5 another SGSN, which will be referred to as an old node, SGSN1. As a result, the new SGSN2 requests MM and PDP contexts for the MS in question from the old SGSN1. All contexts can be requested at the same time, or the MM context and each PDP context can be requested in different messages. The request(s) includes at least the routing area identifier RA_id of the old routing
10 area and the TLLI. The old SGSN1 sends in response an MM context, PDP contexts and possibly authorization parameter triplets. If the MS is not recognized in the old SGSN1, the old SGSN1 replies with an appropriate error message. The old SGSN1 stores the new SGSN2 address until the old MM context has been deleted so that data packets can be relayed from the old
15 SGSN1 to the new SGSN2.

3-3. The new SGSN2 sends a message "Modify PDP Context Request" including e.g. a new SGSN address to the GGSNs concerned. The GGSNs update their PDP context fields and send in response a message
"Modify PDP Context Response".

20 3-4. The new SGSN2 informs the HLR of the change of the SGSN by sending a message "Update Location" including a new SGSN address and an IMSI.

3-5. The HLR deletes the MM context from the old SGSN1 by sending it a message "Cancel Location" including an IMSI. The old SGSN1
25 deletes the MM and PDP contexts and acknowledges this by sending a message "Cancel Location Ack".

3-6. The HLR sends a message "Insert Subscriber Data" including an IMSI and GPRS subscriber data to the new SGSN2. The new SGSN2 acknowledges this by sending a message "Insert Subscriber Data Ack".

30 3-7. The HLR acknowledges the location update by sending a message "Update Location Ack" to the SGSN.

3-8. If the subscriber is also a GSM subscriber (IMSI-Attached), the association between the SGSN and the VLR has to be updated. The VLR address is deduced from the RA information. The new SGSN transmits a
35 message "Location Updating Request" including e.g. an SGSN address and

an IMSI to the VLR. The VLR stores the SGSN address and acknowledges by sending a message "Location Updating Accept".

3-9. The new SGSN2 confirms the presence of the MS in the new routing area RA. If there are no restrictions for registration of the MS for the new RA, the SGSN creates MM and PDP contexts for the MS. A logical link will be established between the new SGSN and the MS. The new SGSN2 replies to the MS with a message "Routing Area Update Accept" including e.g. a new TLLI. This message tells the MS that the network has succeeded in carrying out the update.

10 3-10. The MS acknowledges the new TLLI with a message "Routing Area Update Complete".

The above-described procedures for allocating the TLLI identifiers, performing routing/location area updates and paging the mobile station are based on several years of experience with GSM systems, and they have been found satisfactory. However, these procedures rely on the assumption that the identifier of the SGSN nodes can be derived from the identities of the cells they serve. It is conceivable that in the future this assumption may no longer be valid. For example, one paging area could be handled by several network elements, such as SGSN nodes. Alternatively, one network element could serve many paging areas. This scenario presents two problems, namely:

20 When the mobile station changes its paging area, the new supporting network element may have trouble in determining the old supporting network element on the basis of the paging area identifier. There is also a risk of two supporting network elements allocating the same TLLI to two different mobile stations.

DISCLOSURE OF THE INVENTION

An object of the invention is to minimise the problems and disadvantages resulting from the prior art temporary identity (TLLI/TMSI) allocation method.

30 The basic idea of the invention is that the network element allocating the temporary identity encodes its own identifier, or part of it, into the temporary identity. For example, if the length of the TLLI is 32 bits, a few bits (such as 3, 4 or 5) can be used to identify the network element allocating the TLLI, whereby 8, 16 or 32 network elements, respectively, could support a single routing/paging/location area.

The TLLI according to the invention is used e.g. by a BSC/RNC to determine the network element to which it should send the packets addressed to a certain mobile station. It is also used by any network element receiving an unknown mobile station to determine the identity of the network element currently supporting the mobile station in question.

In addition to solving the above problems, the invention provides a simple and effective way for a base station subsystem (BSS) serving the mobile station to keep track of which network element currently supports the mobile station in question. This is especially useful if a BSS is connected to many network elements.

BRIEF DESCRIPTION OF THE DRAWINGS

In the following, the invention will be described in greater detail by means of preferred embodiments with reference to the accompanying drawings, in which

- Figure 1A illustrates GPRS network architecture;
- Figure 1B illustrates protocol layers of the signalling level between an MS and an SGSN;
- Figure 2 is a signalling diagram illustrating an attach procedure;
- Figure 3 is a signalling diagram illustrating a routing area update procedure; and
- Figure 4 illustrates the concept of a domain name server in connection with a packet radio system.

DETAILED DESCRIPTION OF THE INVENTION

The present invention can be applied to packet radio systems of various kinds. The invention can be used especially preferably for providing a general packet radio service GPRS in the pan-European digital mobile communication system GSM (Global System for Mobile Communication) or in corresponding mobile communication systems, such as the DCS1800 and the PCS (Personal Communication System), or in a more advanced system, such as the UMTS (Universal Mobile Telecommunications System). In the following, the preferred embodiments of the invention will be described by means of a GPRS packet radio network formed by the GPRS service and the GSM system without limiting the invention to this particular packet radio system. For example, in third-generation systems, such as the UMTS, a radio network controller RNC may be used instead of a BSC, etc.

When the MS detects a new cell or a new routing area RA, this means one of four possible cases: 1) a cell update is needed; 2) a routing area update is needed; 3) a combined update of a routing area and a location area is needed, or 4) nothing is needed (the MS is in the standby mode and the RA does not change). In the first three cases the MS selects a new cell locally and stores the cell identity in its MM context.

According to the invention, the attach procedure shown in Figure 2 is modified so that in step 2-8 the ATTACH ACCEPT message comprises the inventive temporary identity (e.g. TLLI) which indicates (i.e. comprises at least part of) the identifier of the SGSN that allocated the temporary identity. In the case of Fig. 2, the TLLI comprises part of the identifier of SGSN2. To put it more precisely, the attach procedure per se is not modified, but the temporary identity sent comprises at least a part of the identity of the network element that allocated the temporary identity.

The use of the inventive temporary identity/TLLI can be seen in step 3-1 of Figure 3. Because the Routing Area Update Request indicates in the TLLI coding the identity of the SGSN node (SGSN1) which allocated the TLLI, the new SGSN2 can deduce the proper SGSN address using the old routing area identity together with the TLLI coding, typically using a database functionality. In the TLLI, a code refers to a unique node for the routing area in question.

A cell update is performed when the MS enters a new cell within the current routing area RA and is in the READY state. If the RA has changed, a routing area update is carried out instead of the cell update.

The cell update procedure is carried out as an implicit procedure at the LLC level, which means that normal LLC information and control frames are used for sending information on crossover to the SGSN. In transmission toward the SGSN, the cell identity is added to the BSSGB packets for all LLC frames in the base station system of the network. The SGSN registers the crossover of the MS, and any further traffic toward the MS is routed via a new cell. In a simple cell update the SGSN does not change, and problems overcome by the invention will not arise.

Naturally, the SGSN may also use another suitable signalling sequence for initiating the establishment of a logical link in the LLC layer or in another protocol layer.

According to the invention, the TLLI of the mobile station indicates the network element that allocated the TLLI. In the example of Figure 3, the TLLI indicates the old SGSN1. Obviously, 3 to 5 bits are not sufficient to unambiguously indicate a large number of SGSN nodes. However, these 3 to 5 bits can be reused in a manner somewhat analogous to a frequency reuse pattern as used in the GSM system, whereby the combination of the routing area of the GPRS system and the inventive TLLI coding can unambiguously determine an SGSN node.

In step 2-2 the new SGSN2 knows the identity of the old SGSN1 even if there is a many-to-many relationship between routing areas and SGSN nodes. This is because the mobile station MS has sent, in the ATTACH REQUEST 2-1, the old TLLI and the RAI. If the MS does not send the old TLLI, then in step 2-3 the MS should be identified.

It is possible that there is no one-to-one relationship between the paging area and the BSC (or RNC) area. According to a preferred embodiment of the invention, the TLLI comprises two identifiers, one indicating the paging area and the other one indicating the BSC/RNC.

The temporary identity or TLLI according to the invention can be linked to a specific network element by means of a suitable database. Alternatively, a network element A receiving a TLLI can derive the corresponding network element B by using the routing area identifier associated with the TLLI, which allows it to send some signalling (such as a location update message) to network element B. Network element B will reply directly if it handles the mobile station itself, or it will forward the signalling to the correct network element.

It is not immediately apparent how the network element A can send signalling to network element B, because A may only know 3 to 5 bits of the identifier of B. There are at least three solutions for this problem: 1) A knows the network element identifier NEI and the routing area identity RAI, which identify B. A practical implementation would be to interrogate a domain name server DNS using a key like "rai.nei@operator.gprs" (see Figure 2). 2) The NEI is not used by the new SGSN. Instead, like in prior art systems the routing area RA is used to derive the old SGSN. The difference from prior art systems is that the MS may not be registered in this SGSN node (i.e. associated with the old RAI by a database functionality) but in another one. In this case, the old SGSN can forward the request to the valid SGSN. More generally, instead

the valid address being retrieved from a database the request is sent to an entity which is able to find the valid address (using the old RAI and the TLLI) and to forward the request to the old SGSN handling the MS. The response could be sent by SGSN3 to SGSN1 directly or via another entity (SGSN2).

- 5 Finally 3) a combination of 1 and 2 can be used, in which case the NEI is part of the TLLI but the SGSN (e.g. by a different manufacturer) is not able to use it. In this case the old SGSN address stored in the domain name server can be replaced by a node address which uses the NEI and the RAI (or the LAI).

Figure 4 illustrates the concept of a domain name server DNS in
10 connection with a packet radio system, such as the GPRS. In step 4-1, an MS sends a Routing Area Update Request to SGSN2 ("the new SGSN"). This request comprises the MS's old Routing Area Index RAI and the TLLI according to the invention. In step 4-2, SGSN2 sends them to a domain name server DNS. Together they form an unambiguous combination and in step 4-3
15 the DNS is able to return the address of SGSN1 ("old SGSN"). In steps 4-4 and 4-5 the new SGSN2 is able to retrieve the SGSN context from the old SGSN1.

In a given paging area, a mobile station can be paged with different identities if it is registered in more than one network element. However, it
20 would be simpler if the mobile station listened to only one identity on the paging channel. Thus, according to a further preferred embodiment of the invention an extended temporary identity or TLLI is used. The extended temporary identity or TLLI comprises up to three identifiers as follows:

the first octet: a network element identifier unique to the paging
25 area;

the second octet: a network element identifier unique to the RNC/BSC;

the remaining octets: a paging identity.

(NB It is only for convenience that the three identifiers are shown as
30 full octets.) The paging identity can be a pseudorandom number co-ordinated by the network. It can be allocated by the BSS/RNC or by a separate master network element. For example, for each routing area RA a single SGSN would allocate all the paging identities valid in that RA. The other SGSN nodes should request the paging identity from this master SGSN. It should be unique
35 to each mobile station so that in order to page a mobile station registered in the paging area in question, it is sufficient to use this paging identity. When a

mobile station which is not yet registered in the paging area is paged, the use of the extended TLLI reduces the risk of collision. For uplink transmission and mobility management signalling, the mobile station should use the extended identity. The NEI that is unique to the paging area should identify the SGSN uniquely. In other words, 3 to 5 bits can identify 2^3 to 2^5 SGSN nodes.

It is not always necessary, in particular in downlink transfer or paging, that the first octet of the extended temporary identity comprises the full network element identifier unique to the paging area. Preferably, only part of the temporary identity is used for downlink transfer and paging. Another way of expressing this is that the TLLI is still the paging identity but the NEI is associated with it.

The inventive NEI can be used as follows. For downlink transfer, the SGSN receiving an MT packet knows the identity of the MS and the cell it is located in. Therefore, downlink packets can be routed to the MS without the inventive NEI. Uplink packets, however, are sent by an MS to a BSC, which may be connected to many SGSN nodes. Thus the MS must send the NEI in every packet to enable the BSC to route the packet to the correct SGSN.

According to a further preferred embodiment, the BSC maintains a context for the MS, in which the relevant SGSN is indicated. However, when the cell or routing area of the MS changes, the BSC serving the MS can change too. Therefore, the MS should insert the NEI in every packet after a cell/routing area change. The first packet sent after a cell/routing area change could be a signalling message, such as a routing area update, or it may be a normal user data packet which can be used in a GPRS system for indicating an implicit cell update.

There may be a requirement that a routing area change must result in a change of the BSC. In such a case, when the routing area changes the SGSN may change as well. Currently, the new SGSN derives the address of the old SGSN on the basis of the old RAI. However, this is not possible if several SGSN nodes serve a single RA. Therefore the MS should include the NEI in an RA Update message so that the new SGSN can find the old SGSN on the basis of the old RAI and the NEI.

In future telecommunications systems, such as wideband CDMA, it is foreseen that an RNC will maintain a context for each MS. However, to allow flexible network planning the paging area border might be different from an RNC area border. For example, two (or more) RNC nodes (RNC1 and RNC2,

not shown) could serve a single paging area but the MS has a context in RNC1 although it is located in the area of RNC2 where it is to be paged. In this case, the mobile station should include the RNC NEI in the paging response. On the basis of the RNC NEI, RNC2 knows that the MS has a context in RNC1
5 and RNC2 should retrieve the context from RNC1.

Also, when two (or more) RNC nodes serve a single paging area and the MS performs a paging area update to a new paging area, this new paging area might be handled by a new RNC. To enable the new RNC to determine the old RNC, the MS should include the RNC NEI in the paging
10 area update message.

If a GPRS network is connected to a radio network using RNC nodes, during RA updating both NEI and RNC NEI should be sent.

Standardization of the GPRS system is not yet final. The present state of the GPRS system is described in the accepted recommendations
15 GSM 03.60 version 6.1.0 and the LLC is described in GSM 04.64, version 6.1.0 of the European Telecommunications Standards Institute (ETSI), which are incorporated herein by reference.

The description only illustrates preferred embodiments of the invention. The invention is not, however, limited to these examples, but it may
20 vary within the scope of the appended claims.

CLAIMS

1. A method of allocating a temporary identity (TLLI) in a cellular network to a mobile station (MS) by a first network element (SGSN, BSC, RNC) which has an identifier of its own, characterized in that the temporary identity (TLLI) comprises at least part of an identifier (NEI) indicating the first network element.

2. A method according to claim 1, characterized in that the temporary identity also comprises a paging identity which is unique to each mobile station in the paging area in question.

3. A method according to claim 1 or 2, characterized in that the identifier (NEI) of the first network element together with an identifier (RAI) of the paging area where said temporary identity was allocated uniquely identifies the first network element.

4. A method according to any one of the preceding claims, characterized in that the cellular network comprises a plurality of paging areas, each paging area having an associated master network element for allocating a paging identity to each of several mobile stations in the paging area; and the first network element, before allocating the temporary identity to a paging area, requests a paging identity for the mobile station from said master network element in the paging area in question.

5. A method according to any one of the preceding claims, characterized in that the cellular network comprises a plurality of paging areas, each of which is connected to a plurality of network elements, and that the cellular network uses said temporary identity for routing uplink traffic to the network element currently serving the mobile station (MS).

6. A method according to any one of the preceding claims, characterized in that the cellular network comprises a plurality of paging areas, and that after a change to a new paging area by the mobile station (MS), a network element to which the mobile station is registered uses said temporary identity and the identifier of the new paging area for deriving an identifier of a network element which served the mobile station before said change.

7. A method according to any one of claims 2 to 6, characterized in that only said paging identity is used at first for paging the mobile station, and that the entire temporary identity is used for signalling.

8. A network element, preferably a support node (SGSN) for a cellular network, adapted to allocate a temporary identity (TLLI) to a mobile station (MS), characterized in that said temporary identity comprises at least a part, preferably 3 to 5 bits, of an identifier (NEI) indicating the network element that allocates the temporary identity.

9. A network element according to claim 8, characterized by being adapted to use said temporary identity (TLLI) and the identifier of the paging area where the mobile station (MS) is located to derive an identifier of another network element which served the mobile station prior to the current network element.

10. A network element according to claim 8 or 9, characterized in that said temporary identity also comprises a paging identity which is unique to each mobile station (MS) in the paging area in question.

11. A cellular network, characterized by a network element according to any one of claims 8 to 10.

12. A cellular network according to claim 11, characterized by a database element, preferably a domain name server (DNS), which is adapted to:

- receive an inquiry comprising said at least part of the identifier of the network element that allocates the temporary identity and information relating to the location where the temporary identity was allocated, such as a paging area identifier; and to

- unambiguously determine, on the basis of said inquiry, an address of the network element which allocated the temporary identity.

13. A cellular network according to claim 12, characterized in that the database element (DNS) is also adapted to send an inquiry to another network element currently storing a context for the mobile station (MS) in question.

14. A mobile station (MS) for a cellular network, being adapted to use a temporary identity (TLLI) allocated by a network element, characterized in that said temporary identity comprises at least a part, preferably 3 to 5 bits, of the identifier of the network element (SGSN) that
5 allocates the temporary identity.

15. A mobile station (MS) according to claim 14, characterized by being adapted to use the temporary identity in connection with at least one of the following procedures:

- cell update,
- 10 - routing area update,
- location area update,
- paging area update, and
- paging response.

16. A mobile station (MS) according to claim 14 or 15,
15 characterized by being adapted to:

use a part of the identifier of the network element (SGSN) that allocates the temporary identity for data transfer; and to use the identifier in full for signalling.

17. A radio station controller, preferably a Base Station Controller
20 (BSC) or a Radio Network Controller (RNC), for a cellular network, adapted to route data packets comprising a temporary identity allocated to a mobile station (MS), characterized in that

the temporary identity comprises at least part, preferably 3 to 5 bits, of an identifier (NEI) indicating a first network element which allocated the
25 temporary identity; and

the radio station controller is adapted to use said at least part of the identifier for routing data packets to said first network element currently serving the mobile station.

18. A radio station controller according to claim 17,
30 characterized by comprising, for each of several mobile stations, a context for temporarily storing an identifier of the network element currently serving the mobile station.

1/3

Fig. 1A





Fig. 1B



2/3

Fig. 2






Fig. 4



3/3

Fig. 3



INTERNATIONAL SEARCH REPORT

International application No.

PC 99/00825

A. CLASSIFICATION OF SUBJECT MATTER

IPC7: H04Q 7/38, H04L 12/56

According to International Patent Classification (IPC) or to both national classification and IPC

B. FIELDS SEARCHED

Minimum documentation searched (classification system followed by classification symbols)

IPC7: H04Q, H04L

Documentation searched other than minimum documentation to the extent that such documents are included in the fields searched

SE,DK,FI,NO classes as above

Electronic data base consulted during the international search (name of data base and, where practicable, search terms used)

EPOQUE: EPODOC

C. DOCUMENTS CONSIDERED TO BE RELEVANT

Category*	Citation of document, with indication, where appropriate, of the relevant passages	Relevant to claim No.
X	EP 0859531 A2 (TELEFONAKTIEBOLAGET LM ERICSSON), 19 August 1998 (19.08.98), column 2, line 3 - column 3, line 4; column 3, line 39 - line 51; column 4, line 12 - line 15 --	1,8, 14 AND 17
A	WO 9916036 A1 (ELDRIDGE, MARTIN, E.), 1 April 1999 (01.04.99), figures 1-4, claims 1-17 --	1-8
A	WO 9733403 A1 (NOKIA TELECOMMUNICATIONS OY), 12 Sept 1997 (12.09.97), figures 1-4, claims 1-18 -- -----	1-18

☐

Further documents are listed in the continuation of Box C.

☒

See patent family annex.

* Special categories of cited documents:

"A" document defining the general state of the art which is not considered to be of particular relevance

"E" earlier document but published on or after the international filing date

"L" document which may throw doubts on priority claim(s) or which is cited to establish the publication date of another citation or other special reason (as specified)

"O" document referring to an oral disclosure, use, exhibition or other means

"P" document published prior to the international filing date but later than the priority date claimed

"T" later document published after the international filing date or priority date and not in conflict with the application but cited to understand the principle or theory underlying the invention

"X" document of particular relevance: the claimed invention cannot be considered novel or cannot be considered to involve an inventive step when the document is taken alone

"Y" document of particular relevance: the claimed invention cannot be considered to involve an inventive step when the document is combined with one or more other such documents, such combination being obvious to a person skilled in the art

"&" document member of the same patent family

Date of the actual completion of the international search

7 March 2000

Date of mailing of the international search report

09-03-2000

Name and mailing address of the ISA:

Swedish Patent Office

Box 5055, S-102 42 STOCKHOLM

Facsimile No. +46 8 666 02 86

Authorized officer

Agneta Änggård/Els

Telephone No. +46 8 782 25 00

INTERNATIONAL SEARCH REPORT

Information on patent family members

02/12/99

International application No.

PCT/FI 99/00825

Patent document cited in search report			Publication date	Patent family member(s)		Publication date
EP	0859531	A2	19/08/98	AU	6225898 A	07/08/98
				NO	970181 A	16/07/98
				WO	9832305 A	23/07/98
				ZA	9800074 A	08/07/98

WO	9916036	A1	01/04/99	NONE		

WO	9733403	A1	12/09/97	AU	2096797 A	22/09/97
				CA	2219256 A	12/09/97
				EP	0824813 A	25/02/98
				FI	102936 B	00/00/00
				FI	960996 A	05/09/97
				JP	11504789 T	27/04/99
